BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE
SCHEDULE - B

Name of Work : .Restoration of Road cut portion done by BWSSB(For Water Line and sanitary Line) in Shettyhalli old village area in Ward No.12, Shettyhalli Sub Division.

NAME OF AGENCY : PROFESSIONAL GLOBLAL INFRASTRUCTURE PVT LTD

Sl No	Description of items	Unit	Qty	Quoted Rate	Quoted Rate in words	Amount in Rupees
1	2	3	4	5	6	7
1	Restoration of road cut portion by removing and desposing all failed material, trimming of completed excavation to provide firm verticle faces, cleaning of surface, strenthening of subgrade, granualar sub base, wetmix macadam including premixing the material with water at OMC, Compaction and finaly applying prime cote, Tack code (900,1200 and 1500 MM width of road cutting,) and Asphalt layer of Bituminous macadam (900,1200 and 1500 MM width of road cutting,) and semidons bituminous concrete and restoration of rain cuts with specific soil as per the specification and drawing. Restoration of roads in Shettyhalli old village area surrounding.					
a	Restoration of road cut portion done by BWSSB in roads under BBMP Limits (110 Villages) (750mm width of road cutting)	Per mtr	310.00	785.33	Rupees Seven Hundred Eightyfive Paise Thirtythree Only	243452.30
b	Restoration of road cut portion done by BWSSB in roads under BBMP Limits (110 Villages) (900mm width of road cutting) for Water Line	Per mtr	3967.00	957.75	Rupees NineHundred Fiftyfive Paise seventyfive Only	3799394.25
c	Restoration of road cut portion done by BWSSB in roads under BBMP Limits (110 Villages) (1200mm width of road cutting) for sanitary Line	Per mtr	3850.00	1254.05	Rupees Onethousand Twohundred Fiftyfoure paise Five Only	4828092.50
	Grand Total					**8870939.05**

For Professional Global Infrastructure Pvt. Ltd.

Contractor

Executive Engineer
Dasarahalli Division
BBMP, Bengaluru

Scanned by CamScanner